PROPERTY MAP

PCL	OWNER
3	NOT REQUIRED
4	ROSA LEE HOPKINS
6	THE FELLOWSHIP SPIRITUAL CHURCH
7	ELIZABETH A. JEMISON
8	IBERER WALLACE
9	P. AND H. REALTY CO., INC.
10	HARRY ANDREW SMYERS & HERBERT ALFRED SMYERS
11	ELIZABETH STEIN
12	THE LIEBMAN-SWANEY REALTY COMPANY
12A	"
12B	"
13-A	NOT REQUIRED
15	J. & S. INVESTMENT, A PARTNERSHIP
16	WILLIAM E. VERI, JR. & RONALD J. SIBERA, SR.
16A	WILLIAM E. VERI, JR. & RONALD J. SIBERA, SR.
17	ROGER J. BAHM & HOWARD W. WISWELL
18	CONSOLIDATED RAIL CORPORATION (MAHONING COAL RAILROAD COMPANY)(CLEVELAND AND MAHONING VALLEY RAILWAY COMPANY)
18A	"
18B	"
19	REPUBLIC STEEL CORPORATION
20	THE HABUDA COAL AND SUPPLY CO.
21	THE CITY OF YOUNGSTOWN
21A	"
22	NEW ZION GOSPEL CHURCH

23	ANDREW ALLEN & MILDRED ALLEN
24	STATE OF OHIO, DEPARTMENT OF TRANSPORTATION
25	NATASHA BLAIR
26	ANTHONY ZARLENGA
26A	"
27	LULU GREEN & NEWTON GREEN
28	JAMES R. ROBINSON & EMMA J. ROBINSON

CALC BY J.A.B. DATE 11/86
CHKD BY A.D.W. DATE 11/86

CITY OF YOUNGSTOWN
MAH.-289-1.51
OAK ST.

OHIO
FHWA REGION 5

FEDERAL PROJECT | M-2A48(1) | STATE PROJECT

76/84
1/9

MATCH LINE 'A'

MAHONING COUNTY
YOUNGSTOWN TOWNSHIP
CITY OF YOUNGSTOWN
T-2N, R-2W

EXIST. LA

O.L. B20

MATCH LINE 'A'

CURVE DATA
℄ OAK ST.
P.I. STA. 11+13.20
Δ = 30°05'00" (LT.)
R = 818.51'
D_c = 7°00'00"
T = 219.96'
L = 429.74'
E = 29.03'

CURVE DATA
℄ ELK ST.
P.I. STA. 150+00.00
Δ = 30°04'30" (LT.)
R = 150.78'
D_c = 38°00'00"
T = 40.51'
L = 79.15'
E = 5.35'

CURVE DATA
℄ OAK ST.
P.I. STA. 26+73.67
Δ = 2°58'55"
R = 3841.99'
D_c = 1°29'29"
T = 100.00'
L = 199.96'
E = 1.30'

BEGIN WORK
STA. 148+25.00

WATT ST.

EXIST. R/W

ADAMS ST.

MEADOW ST.

EXIST. R/W

STA. 12+21.89 ℄ OAK ST. =
STA. 49+97.78 ℄ W. RAVEN AVE.

STA. 139+44.11 ℄ OAK ST. =
STA. 50+73.65 ℄ E. RAVEN AVE.

STA. 154+15.05 ℄ OAK ST. =
STA. 102+57.07 ℄ ANDREWS AVE.
STA. 151+43.97 ℄ ELK ST.

STA. 179+16.49 ℄ OAK ST. =
STA. 123+36.42 ℄ ANDREWS AVE.
STA. 51+83.41 ℄ ELK ST.

ANDREWS AVE.

EXIST. R/W

CRAB CREEK

CONRAIL R.R.

O.L. 534

O.L. 820

O.L. 25

END PROJECT
STA. 24+50.00
M-2A48(1)

END WORK
STA. 25+10.38

SUSPEND WORK
STA. 151+18.00

RESUME WORK
STA. 151+69.19

END WORK
STA. 154+28.00

PC STA. 251+73.67

PT STA. 27+13.63
℄ MAH.-7-15.95

STA. 28+21.43 ℄ OAK ST. =
STA. 859+88.11 ℄ MAH.-7-15.95

N86°55'05"E

79°49'21"

OAK ST.

N89°54'00"E

90°21'53"

EXIST. R/W

JACKVILLE ST.

EXIST. R/W

NINE

N00°31'53"W

EXIST. R/W

EXIST. R/W

PENN AVE.

EXIST. R/W

CRAB CREEK

CONRAIL R.R.

O.L. 809

BEGIN PROJECT
STA. 11+00.00
M-2A48(1)

BEGIN WORK
STA. 8+45.00

S60°01'00"E

OAK ST.

S31°59'00"W

WATT ST.

BEGIN ACQUISITION
STA. 10+95.18

STA. 12+16.84 ℄ OAK ST. =
STA. 49+97.78 ℄ E. RAYEN AVE.

EXIST. R/W

VIA MT. CARMEL

EXIST. R/W

E. WOOD ST.

STA. 8+10.07 ℄ OAK ST. =
STA. 50+00 ℄ WATT ST.

PC STA. 8+93.24

EXIST. R/W

EXIST. R/W

ELK

EXIST. R/W

MEADOW ST.

EXIST. R/W

EXIST. R/W

EXIST. R/W

ANDREWS AVE.

EXIST. R/W

EXIST. R/W

CRAB CREEK

CONRAIL R.R.

EXIST. R/W

EXIST. R/W

PENN AVE.

EXIST. R/W

CURVE DATA
℄ E. RAYEN AVE
P.I. STA. 51+42.64
Δ = 59°55'51" (LT.)
R = 32.00'
T = 18.45'
L = 33.47'
E = 4.94'

STA. 54+85.98 ℄ E. RAYEN AVE. =
STA. 100+06.30 ℄ ANDREWS AVE.

END WORK
STA. 54+65.00

MAHONING COUNTY
YOUNGSTOWN TOWNSHIP
CITY OF YOUNGSTOWN
T-2N, R-2W

STA. 25+73.67 ℄ OAK ST. =
STA. 30+00 ℄ HINE ST.

END ACQUISITION
STA. 25+79.39

AFFECTED UTILITIES

THE EAST OHIO GAS CO.
1717 EAST NINTH ST.
CLEVELAND, OHIO 44114
1-216-623-4709

OHIO EDISON CO.
76 SOUTH MAIN ST.
AKRON, OHIO 44308

OHIO BELL TELEPHONE CO.
2405 MARKET ST.
YOUNGSTOWN, OHIO 44507
744-6950

WATER DEPT. CITY OF YOUNGSTOWN
CITY HALL BOARDMAN & PHELPS
YOUNGSTOWN, OHIO 44503
746-1892

SEWER DEPT. CITY OF YOUNGSTOWN
CITY HALL BOARDMAN & PHELPS
YOUNGSTOWN, OHIO 44503
746-1892

SCALE
0 100 200 300 400

Revised
Sheet Completed Date: 1/13/86
R/W to

PROPERTY MAP